

# Tree Survey Report Sheet

Site: Buncrana Leisure Centre

Client: Kennedy Fitzgerald Architects

Tag No.	Species	Height (m)	Stem Diameter (mm)	Crown spread (m)				Crown Clearance (m)	Age	General Observations				Action	ULE	Category	Priority	Target
				N	E	S	W			Crown form	Condition	Defect	Obstacle					
T1	Cabbage palm	5	220	2	1	2	2	2	AM	3 stems from the ground	Fair	None	None	<b>No action is required</b>	More than 40	B1	Not applicable	High, road or building
T2	Sycamore	12	600	5	6	5	4	1	AM	3 stems from 1.0m, Spreading crown	Fair	None	Path, Road, Buildings	<b>Remove ivy, Crown lift to 2.4m over path, Crown lift to 2.4m over lawn, Crown lift to 5.1m over road, Clear back from building</b>	More than 40	B1	Medium	High, road or building
T3	Sycamore	7	280	3	4	3	3	1	YM	Multi stem from 2.0m, Recently trimmed	Fair	None	Path	<b>Crown lift to 2.4m over path, Crown lift to 2.4m over lawn</b>	More than 40	B1	Medium	High, road or building
T4	Sycamore	5	220	2	3	2	2	1	YM	Single main stem with heavy side branches, Recently trimmed	Fair	None	Path	<b>Crown lift to 2.4m over path, Crown lift to 2.4m over lawn</b>	More than 40	B1	Medium	High, road or building
T5	Sycamore	5	270	3	4	4	3	1	YM	Multi stem from 2.0m, Spreading crown, Recently trimmed	Fair	None	Path	<b>Crown lift to 2.4m over path, Crown lift to 2.4m over lawn</b>	More than 40	B1	Medium	High, road or building
T6	Beech	5	180	3	2	3	1	1	Y	Multi stem from 1.0m, Spreading crown	Fair	None	None	<b>Crown lift to 2.4m over lawn</b>	More than 40	B1	Routine	Medium, path or lawn
T7	Oak	9	190	2	3	3	3	2	Y	Single main stem with heavy side branches	Fair	None	None	<b>No action is required</b>	More than 40	B1	Not applicable	High, road or building
T8	Oak	9	210	4	4	3	2	1	Y	Single main stem with heavy side branches	Fair	None	None	<b>Crown lift to 2.4m over lawn</b>	More than 40	B1	Routine	Medium, path or lawn
T9	Oak	9	170	3	2	2	3	1	Y	Multi stem from 2.0m	Fair	None	None	<b>Crown lift to 2.4m over lawn</b>	More than 40	B1	Routine	Medium, path or lawn
T10	Oak	8	220	2	3	2	2	1	Y	2 stems from 1.0m, Spreading crown	Fair	None	None	<b>Crown lift to 2.4m over lawn</b>	More than 40	B1	Routine	Medium, path or lawn
T11	Oak	9	230	3	4	2	2	2	Y	Single main stem with heavy side branches	Fair	None	None	<b>No action is required</b>	More than 40	B1	Not applicable	Low unmanaged or farmland

ULE: Estimated and approximate Useful Life Expectancy

# Tree Survey Report Sheet

Site: Buncrana Leisure Centre

Client: Kennedy Fitzgerald Architects

Tag No.	Species	Height (m)	Stem Diameter (mm)	Crown spread (m)				Crown Clearance (m)	Age	General Observations				Action	ULE	Category	Priority	Target
				N	E	S	W			Crown form	Condition	Defect	Obstacle					
G12	Goat willow	7	220	1	4	2	3	2	M	2 stems from the ground, Recently trimmed	Fair	None	None	<b>No action is required</b>	20 to 40	B1	Not applicable	High, road or building
T13	Bay willow	9	330	3	2	2	3	2	M	3 stems from the ground, Recently trimmed	Fair	None	None	<b>No action is required</b>	10 to 20	B1	Not applicable	High, road or building
T14	Goat willow	5	170	1	3	1	0	2	AM	2 stems from 1.0m, Recently trimmed	Fair	None	None	<b>No action is required</b>	20 to 40	B1	Not applicable	High, road or building
T15	Goat willow	5	100	1	2	2	2	0	SM	Multi stem	Fair	None	Buildings	<b>Clear back from building</b>	20 to 40	B1	Routine	High, road or building
G16	Sycamore	13	450	4	3	5	5	4	AM	Multi stem, Recently trimmed	Fair	None	None	<b>No recommendations are given</b>	More than 40	B1	Not applicable	High, road or building
T17	Sycamore	16	730	2	6	6	6	2	M	2 stems from 4.0m, Leaninhg	Fair	None	Buildings	<b>Crown clean, Clear back from building</b>	20 to 40	B1	High	High, road or building
T18	Sycamore	16	530	5	5	3	4	2	M	Single main stem with heavy side branches	Fair	None	Path, Buildings	<b>Crown lift to 2.4m over path, Clear back from building</b>	More than 40	B1	Medium	High, road or building
T19	Sycamore	18	780	4	5	6	4	5	M	Single stem to 6.0m	Poor	Excessive deadwood	None	<b>Monitor for death, Crown clean, Reduce end weight in top and side branches by 1.0m</b>	20 to 40	C1	High	High, road or building
T20	Sycamore	0	380	0	0	0	0	0	-	0	Dead	Dead	0	<b>Fell</b>	Less than 10	U	High	High, road or building
T21	Sycamore	14	450	2	2	5	3	2	M	Single main stem with heavy side branches, Leaninhg	Poor	Recent crown failure	Buildings	<b>Crown clean, Clear back from building, Reduce end weight in top and side branches by 1.0m</b>	20 to 40	C1	High	High, road or building

ULE: Estimated and approximate Useful Life Expectancy

# Tree Survey Report Sheet

Site: Buncrana Leisure Centre

Client: Kennedy Fitzgerald Architects

Tag No.	Species	Height (m)	Stem Diameter (mm)	Crown spread (m)				Crown Clearance (m)	Age	General Observations				Action	ULE	Category	Priority	Target
				N	E	S	W			Crown form	Condition	Defect	Obstacle					
T22	Sycamore	14	530	5	4	5	2	3	M	Single main stem with heavy side branches	Poor	Thinning crown, Hollow	Buildings	<b>Crown clean, Clear back from building, Reduce end weight in top and side branches by 2.0m</b>	10 to 20	C1	High	High, road or building
T23	Sycamore	14	470	5	4	5	2	2	M	Single main stem with heavy side branches	Fair	None	Buildings	<b>No recommendations are given</b>	More than 40	B1	Not applicable	High, road or building
G24	Goat willow	6	250	5	0	0	0	1	AM	Multi stem	Fair	None	Buildings, Wall, Fence	<b>Clear back from building, Clear back from wall, Clear fence</b>	20 to 40	B1	Medium	High, road or building
T25	Norway maple	8	480	2	3	5	5	1	AM	Multi stem from 1.0m, Spreading crown	Fair	None	Path, Fence	<b>Remove ivy, Crown lift to 2.4m over path, Clear fence</b>	20 to 40	B1	Medium	High, road or building
T26	Sycamore	8	220	3	4	2	2	2	SM	Single main stem with heavy side branches	Fair	None	None	<b>No action is required</b>	More than 40	B1	Not applicable	Medium, path or lawn
T27	Sycamore	10	340	2	5	5	3	2	AM	Multi stem from 2.0m, Spreading crown, One sided crown	Fair	None	Path	<b>Crown lift to 2.4m over path, Crown lift to 2.4m over lawn</b>	More than 40	B1	Routine	High, road or building
G28	Cabbage palm	2	100	1	2	1	2	1	SM	Multi stem	Fair	None	None	<b>No action is required</b>	20 to 40	B1	Not applicable	High, road or building
G29	Cabbage palm	2	80	1	1	1	1	0	SM	2 stems from the ground	Fair	None	None	<b>No action is required</b>	20 to 40	B1	Not applicable	High, road or building
G30	Cabbage palm	3	100	1	1	1	1	2	SM	3 stems from the ground	Fair	None	None	<b>No action is required</b>	20 to 40	B1	Not applicable	High, road or building
T31	Cabbage palm	2	70	1	1	1	1	0	SM	Single stem	Fair	None	None	<b>No action is required</b>	More than 40	B1	Not applicable	High, road or building
G32	Cabbage palm	2	80	1	2	1	1	1	SM	Multi stem	Fair	Thinning crown	None	<b>Fell dead and dying stems</b>	20 to 40	B1	Routine	High, road or building
G33	Cabbage palm	2	80	2	2	2	1	1	SM	Multi stem	Fair	None	None	<b>No action is required</b>	20 to 40	B1	Not applicable	High, road or building

ULE: Estimated and approximate Useful Life Expectancy

# Tree Survey Report Sheet

Site: Buncrana Leisure Centre

Client: Kennedy Fitzgerald Architects

Tag No.	Species	Height (m)	Stem Diameter (mm)	Crown spread (m)				Crown Clearance (m)	Age	General Observations				Action	ULE	Category	Priority	Target
				N	E	S	W			Crown form	Condition	Defect	Obstacle					
T34	Alder	7	370	3	1	3	3	0	M	Single main stem with heavy side branches, Recently trimmed	Fair	None	None	<b>No action is required</b>	20 to 40	B1	Not applicable	Medium, path or lawn
T35	Alder	8	480	2	3	5	2	0	M	2 stems from 1.0m, Spreading crown, Recently trimmed	Fair	None	None	<b>No action is required</b>	20 to 40	B1	Not applicable	Medium, path or lawn
T36	Alder	7	470	5	5	5	2	0	M	2 stems from 1.0m, Spreading crown, Recently trimmed	Fair	None	None	<b>No action is required</b>	20 to 40	B1	Not applicable	Medium, path or lawn
T37	Alder	6	260	4	2	4	4	1	M	2 stems from the ground, Spreading crown, Recently trimmed	Fair	Thinning crown	None	<b>No action is required</b>	10 to 20	B1	Not applicable	Medium, path or lawn
T38	Alder	6	280	3	1	3	2	1	AM	2 stems from 1.0m	Fair	None	None	<b>No action is required</b>	20 to 40	B1	Not applicable	Medium, path or lawn
T39	Alder	6	170	3	2	3	2	0	AM	Single main stem with heavy side branches, Recently trimmed	Fair	None	None	<b>No action is required</b>	20 to 40	B1	Not applicable	Medium, path or lawn
T40	Alder	7	410	4	3	5	2	1	M	Single main stem with heavy side branches, Recently trimmed	Fair	None	None	<b>No action is required</b>	20 to 40	B1	Not applicable	Medium, path or lawn
T41	Alder	6	200	3	2	3	3	0	AM	Single main stem with heavy side branches	Fair	None	None	<b>No action is required</b>	20 to 40	B1	Not applicable	Medium, path or lawn
T42	Alder	7	340	4	2	4	4	2	M	Multi stem from 3.0m, Spreading crown, Recently trimmed	Fair	None	None	<b>No action is required</b>	20 to 40	B1	Not applicable	Medium, path or lawn
T43	Alder	7	330	4	3	5	2	2	M	2 stems from the ground, Recently trimmed	Fair	Thinning crown	None	<b>Crown clean</b>	10 to 20	B1	Medium	Medium, path or lawn
T44	Alder	7	260	2	4	4	2	1	M	Single main stem with heavy side branches, Recently trimmed	Fair	None	Overhead telephone cables	<b>Clear overhead cables</b>	20 to 40	B1	Routine	High, road or building

ULE: Estimated and approximate Useful Life Expectancy

# Tree Survey Report Sheet

Site: Buncrana Leisure Centre

Client: Kennedy Fitzgerald Architects

Tag No.	Species	Height (m)	Stem Diameter (mm)	Crown spread (m)				Crown Clearance (m)	Age	General Observations				Action	ULE	Category	Priority	Target
				N	E	S	W			Crown form	Condition	Defect	Obstacle					
T45	Sycamore	9	470	5	5	3	4	2	AM	Single main stem with heavy side branches, Spreading crown	Fair	None	Path	<b>Crown lift to 2.4m over path</b>	<i>More than 40</i>	<i>B1</i>	<i>Routine</i>	<i>High, road or building</i>

ULE: Estimated and approximate Useful Life Expectancy